

Alignment for the ALBA Project



Fabien Rey

CELLS - ALBA

Edifici Ciències Nord. Mòdul C-3 central.

Universitat Autònoma de Barcelona


08193 Bellaterra,

BARCELONA - SPAIN

Outline


- ❖ *The ALBA Project*
- ❖ *Instrumentation*
- ❖ *Alignment Procedures*
- ❖ *Schedule*

▪ Geographical Location



Barcelona (Catalunya)

ALBA parcel



Institut Cartogràfic
de Catalunya

The ALBA Project

- 3D visualization



▪ Main parameters of the Synchrotron:

➤ **Injector:**



Linac:

Energy	100 Mev
Emittance	$\leq 50 \text{ mm.mrad}$
Length	15 m


➤ **Storage Ring:**

Booster:

Peak energy	3 Gev
Circumference	249.6 m
Current	2 mA

Emittance	4.5 nm*rad
Energy	3 Gev
Circumference	268.8 m
Maximum beam current	400 mA

The ALBA machine:



Tunnel Section


DBA structure lattice

straight sections:

4 of 8 meters


14 of 4.2 meters

8 of 2.6 meters




The ALBA Project

- The ALBA machine:



The ALBA Project

- The ALBA machine:




The ALBA Project

- The ALBA machine:

Fourfold symmetric
268.8 m circumference

6 types of girders
3 pedestals/girder


Storage Ring



Y.Nikitin
R.Valcarcel

The ALBA Project


▪ The ALBA machine:



Y.Nikitin
R.Valcarcel


The ALBA Project

- The ALBA machine:



▪ Storage Ring Positioning Specifications

	Combined bending magnet	Quad & Sext	Girder/Girder
σ_i	30 μm	30 μm	100 μm
σ_j	200 μm	200 μm	200 μm
σ_k	30 μm	30 μm	100 μm



	Combined bending magnet	Quad & Sext	Girder/Girder
$\sigma_{\theta i}$	--	--	--
$\sigma_{\theta j}$	500 μrad	200 μrad	250 μrad
$\sigma_{\theta k}$	--	--	--

our constraints:

- 270m machine.
- One single tunnel with both Booster and Storage Ring.
- Front End and Beam Lines encumbered.
- Geotechnical conclusions promising.
- Budget and Man Power.
- Fiducialization relying on accurately machined features.

Call for tender:

Lot n°2: *Electronic Theodolite*

Lot n°1: *Total Station*


Lot n°3: *Laser Tracker*

Lot n°4: *Portable 3D Measurement Arm*

Lot n°5: *Industrial Metrology Software*


Others: - *Optical Level*
- *Digital Level*

Alignment Procedures



Institut Cartogràfic de
Catalunya

Alignment Procedures



Institut Cartogràfic de
Catalunya



Alignment Procedures

13 references marks on the slab

5 in the Experimental Hall

5 in the Tunnel


3 in the LINAC



Alignment Network

Tunnel: 54 references on the ground
106 references on the walls


Experimental hall: 20 references / Beamline
(first on the slab, and then on the walls)



Network Simulation

- 54 floor references
- 106 wall references
- 53 stations
- at least 9 common points between 2 stations
- 12 reference points measured for each station




Maximum estimated radial
standard deviation: ± 0.08 mm



F.Guilharretze - CABAB

Standard error ellipse

Fiducialization



- ❖ one machined hole for receiving 1.5" reflector adapter.

Schedule

2006	<ul style="list-style-type: none"> ▪ June – Start of the building construction and site urbanization 				
2007	<ul style="list-style-type: none"> ▪ Feb – Slab ready for installation of Alignment Reference Network 				
2008	<p style="color: blue;">Installation / Commissioning LINAC</p> <p style="color: blue;">Sept</p> <p style="color: blue;">Nov</p> <p style="color: blue;">April</p> <p style="color: blue;">Oct</p> <p style="color: blue;">Installation Booster/TL</p> <p style="color: blue;">April</p> <p style="color: blue;">Oct</p> <p style="color: blue;">Installation SR + FE</p> <p style="color: blue;">Sept</p> <ul style="list-style-type: none"> ▪ April – Tunnel ready for installation ▪ June – Building finished 				
2009	<p style="color: blue;">ID Installation / Commissioning</p> <p style="color: blue;">Oct</p> <p style="color: blue;">Jun</p> <p style="color: blue;">Commissioning Booster/TL/Storage Ring</p> <p style="color: blue;">Jun</p> <p style="color: blue;">Nov</p> <p style="color: blue;">Installation 7 Beam lines</p>				
2010	<p style="color: red;">★ First User</p> <p style="color: blue;">Commissioning</p> <p style="color: blue;">July</p>				

➤ Next Steps

- ❖ Oct 2006 – Tendering Closed
- ❖ Dec 2006 – Delivery of the Instrumentation
- ❖ 2007....

Administration

- Hiring of a Junior Topographic Engineer

Workshop

- Training with Instrumentation
- Checkout of the girder prototype
- Magnets Fiducialization

Site

- Installation/Measurement of the Alignment Network
- Preparation of the Tunnel for Installation (drilling holes, marks...)
- LINAC installation





Thanks for your attention.

