


# PEP-II B Factory Machine Status and Upgrades

John T. Seeman  
for the PEP-II Staff  
SLAC DOE Site Review  
April 9, 2003

# PEP-II Topics

- ◆ FY2002 Results
- ◆ FY2003 Results (first half)
- ◆ FY2003 Plans (second half)
- ◆ FY2004 Plans and Long Range Plans

# PEP-II $e^+e^-$ Collider



PEP-II is a two ring  $e^+e^-$  asymmetric collider



# FY2002 Results

- ◆ Run 2 ended June 30, 2003.
- ◆ Total integrated luminosity (delivered) =  $101 \text{ fb}^{-1}$ .
- ◆ Highest luminosity =  $4.63 \times 10^{33} \text{ cm}^{-2} \text{ s}^{-1}$ .
- ◆ Down was 4.5 months long for BaBar IFR repairs and PEP-II IP cooling upgrades.
- ◆ Run 3 started November 15, 2003.

# 2002 Down Time Projects


## ◆ Major projects finished:

- Support tube bellows cooling (x5 cooling)
- Forward Q2 chamber (new)
- HER #6 RF station (new)
- HER #7 RF station (new)
- IR2 valve repairs
- IR2 valve gap rings (repaired)
- IR2 LER collimator shielding (new)
- Shortened abort kicker gaps (5% → 2.5%)
- New x-y BPMs at ring sextupoles.

# Forward Cooling Collars




# Forward Vertex Chamber Bellows Cooling Installation





# New Q2 chamber





New PEPII forward Q2 vacuum chamber

# IR2 Valve HOM Damage






# PEP-II IR2 Vacuum Valve




# Shortened Abort Gap



## PEP-II FY2003 Run Status (half way)

- ◆ Turn-on started November 15.
- ◆ Winter shutdown December 23-January 1.
- ◆ Power outages (spikes) in December caused hardware damage and run delays.
- ◆ Running has now stabilized.
- ◆ Present data run will end June 30.
- ◆ Run 4 starts September 5, 2003.
- ◆ Run 4 stops July 11, 2004, for 10 months.
- ◆ Recall that SPEAR-3 is installed this summer.


# PEP-II Energy width measured on the Upsilon 3S resonance



# Recent Accelerator Advances

- ◆ By-4 bunch pattern of last spring had very little room to add bunches. Now with By-3 pattern and mini-trains we have open slots to expand the number of bunches and increase the currents. By-3 pattern has extra HOM heating.
- ◆ Poor beam orbits from last spring have been fixed but lowered the luminosity. Restored with selected orbit bumps in LER chicanes and sextupoles have reduced the electron cloud effect, vertical dispersion, and horizontal dispersion. (We now, mostly, know why the orbits had to be poor last spring.)
- ◆ Shortened Abort Gap has allowed 2.5% more bunches and smoother RF operation.


I HER	I LER	Luminosity	Spec Lum	E HER	E LER	E CM
899.82	1465.49	4631	3.26	8993	3121	10595
mA	mA	$10^{30}/\text{Sec}$	$N \cdot 10^{30} / \text{mA}^2/\text{Sec}$	MeV	MeV	MeV
HER N Buckets / Pattern			LER N Buckets / Pattern			
921	by3_t10_10_9_her_ratio		928	by3_t10_10_9_ler		
Last Owl/Day/Swing/24hr		117.0	112.1	117.9	347.0	Shift: 23.02 /pb
Peak Luminosities		5105	5075	5103	5037	




03/17/2003 09:30:32




## Peak PEP-II Luminosity (x1E33) per Month



# PEP-II Monthly Integrated Luminosity




# PEP-II Daily Average for each Month




# Predicted Integrated Luminosity FY2003

PEP-II Integrated Luminosity for Run 2002-2003							J. Seeman		Dec 4, 2002		
Year	Month	Days	Peak to Average Luminosity Ratio	Peak luminosity xE33 (at end)	Integrated luminosity per period fb-1	Cumulative integrated luminosity fb-1	Positron current (mA)	Electron current (mA)	Beta y*	Beta x*	Number bunches
2002	November	15	0.20	2.1	0.3	0.3	1100	650	1.20	50	642
2002	December	22	0.45	3.5	2.4	2.7					
2003	January	27	0.45	4.5	4.2	6.9	1800	1000	1.20	50	800
2003	February	28	0.45	5.0	5.2	12.0					
2003	March	31	0.45	5.5	6.3	18.4	2200	1100	1.00	47	950
2003	April	30	0.45	6.0	6.7	25.1					
2003	May	31	0.45	6.5	7.5	32.6					
2003	June	30	0.43	7.0	7.5	40.1					
2003	July	31	0.40	7.5	7.8	47.9	2500	1300	0.90	45	1050

# Total PEP-II Delivered Luminosity



# PEP-II Total Delivered Luminosity for 2003



# PEP-II Records

Last update:  
Apr. 1, 2003

## Peak Luminosity

**$5.213 \times 10^{33}$**  cm<sup>-2</sup>sec<sup>-1</sup>

921 bunches    1850 mA LER    960 mA HER

**March 24, 2003**

## Integration records of delivered luminosity

<b>Best shift (8hrs)</b>	<b>119.9</b> pb <sup>-1</sup>	<b>Mar 23, 2003</b>
<b>Best 3 shifts in a row</b>	<b>347.0</b> pb <sup>-1</sup>	<b>Mar 16-17, 2003</b>
<b>Best day</b>	<b>326.1</b> pb <sup>-1</sup>	<b>Mar 16, 2003</b>
<b>Best 7 days</b>	<b>2.062</b> fb <sup>-1</sup>	<b>Mar 20-26, 2003</b>
<b>Best week</b> (Sun 0:00 to Sat 24:00)	<b>2.023</b> fb <sup>-1</sup>	<b>Mar 16-22, 2003</b>

# Luminosity Equation

- ◆ When vertical beam-beam parameter limited.
- ◆  $\xi_y \sim 0.06$  in PEP-II and KEKB.
- ◆ To raise luminosity: lower  $\beta_y^*$ , raise I &  $\xi_y$ .

$$\xi_y^+ = \frac{r_0 N_b^- \beta_y^{*+}}{2\pi \gamma^+ \sigma_y^{*-} \sigma_x^{*-}} \text{ (flatbeams)}$$

$$L = 2.17 \times 10^{34} \frac{n \xi_y E I_b}{\beta_y^*}$$



# FY2003 (second half of year)

## Luminosity Improvements to PEP-II

- ◆ New ring correction algorithms (MIA) –Now works globally to fix beta beats and coupling. So far does not work locally (IR).
- ◆ New local  $\beta_y^*$  knobs in HER/LER. HER works and LER to be tried this week. Try for 9 mm.
- ◆ Move horizontal tunes to near half integer. We will try soon as MIA now works globally.
- ◆ Increase number of bunches and currents. Need to watch RF trips, vacuum heating, and backgrounds.
- ◆ Try continuous injection.


# Scaling factors:

- ◆ Lower  $\beta_y^*$  in HER/LER with luminosity gain = 12/9 or  $\sim x1.25$ . "Difficulty = low to medium"
- ◆ Raise currents and number of bunches by  $x1.3$ . "Difficulty = hard" (several over heating components)
- ◆ Move tunes to half integer to get lower tune shifts. Gain is about  $x1.25$ . "Difficulty = medium to hard"
- ◆ Continuous LER injection: "Difficulty: easy for PEP-II; hard for BaBar". Gain in integrated luminosity is about  $x1.2$ .
- ◆ Total luminosity gain is  $x2.0$ . Hope to get  $x1.4$  by July. (Luminosity to 7.0 by July with more later.)

# PEP-II Summer 2003 Projects

- ◆ New HER # 8 RF station (+200 mA).
- ◆ New HER collimator (30 m upstream).
- ◆ New Longitudinal feedback kickers.
- ◆ Improved transverse feedback kickers.
- ◆ Improved low level RF feedback circuits (higher I).
- ◆ More x-y BPMs in IR2 region.
- ◆ LER straight section and Arc 11 solenoid upgrade.
- ◆ Octupoles for tune shift with amplitude studies.
- ◆ Bellows fans on all LER bellows (~240)
- ◆ Fix IR vacuum gate valves
- ◆ Air cooling of Feedback Kicker cables
- ◆ More background shielding of PEP-II in IR2

# HER Collimator




# Old Longitudinal Kicker






# New Longitudinal Feedback Kicker Assembly



# New Longitudinal Feedback Kicker End Plug



# Transverse Feedback Kicker





# Octupole Magnets (from CERN)




# FY2004 and longer plans

- ◆ Continue to increase luminosity each year → AIP funding (Accelerator Improvement Projects)
- ◆ Big upgrade in the summer of FY 2004 by moving quadrupoles closer to the interaction region and lowering  $\beta_y^*$  to 6-7 mm.
- ◆ Continue to add RF stations (one station per year for five years)
- ◆ Some higher power vacuum chamber upgrades needed.
- ◆ Better beam controls needed: bunch-by-bunch feedbacks, injection, backgrounds, Electron Cloud Instability,...

# PEP-II upgrade with Permanent Magnet Quadrupoles

Possible  $3 \times 10^{34}$  Interaction Region  
with a  $\pm 3.25$  mrad Xangle



# Path to higher PEP-II luminosity

◆ Luminosity	<u>4.8E33</u>	<u>7.5E33</u>	<u>1.5E34</u>	<u>2.5E34</u>	<u>Units</u>
◆ I+	1650	2400	3300	4500	mA
◆ I-	950	1250	1600	2000	mA
◆ Beta y*	14	10	8.0	6.5	mm
◆ Beta x*	50	50	50	50	cm
◆ Bun. Length	1.3	1.05	0.9	0.8	cm
◆ # bunches	898	1180	1450	1700	
◆ Vert. emit	2.5	1.4	0.9	0.9	nm
◆ Horiz. Emittance	40/50	35/45	35/45	40/53	nm (+/-)
◆ Crossing angle	0	0	0	+/-8 (?)	mrad
◆ Beam-beam para.(x/y)	7.5/4.2	7.5/4.4	7.5/5.6	8.2/5.8	x100
◆ Number RF stations	7	10	13	15	
◆ Date hardware ready	Nov 02	Mar 03	Nov 05	Nov 07	
◆ Date for luminosity	Feb 03	July 03	Fall 06	Fall 08	

PEP-II Eight Year Run Plan for FY2003 Thru FY2010												J. Seeman	Jan 13, 2003		
Year	Months	Days	Average to peak lumin. ratio	Peak luminosity xE33 (at end)	Integrated luminosity per period fb-1	Cumulative integrated luminosity fb-1	e+ current (mA)	e- current (mA)	Beta y* (cm)	Beta x* (cm)	Emit horiz (nm) +/-	B-B tune shift (vert/horiz)	Num Bunch	Cont. Inj. factor	MD time factor
	Start		0.5	4.4		103.0	1675	975	12.5	50	25/50	0.035/0.07	762	1.00	0.95
2003	Jan-July	200	0.5	7.53	46.4	149.4	2400	1250	10	50	30/50	0.044/0.073	1180	1.00	0.90
2003	Aug-Sept	60	0	0	0.0	149.4									
2003	Oct-Dec	80	0.4	7.53	10.4	159.8									
2004	Jan-June	170	0.55	11.4	72.3	232.0	2700	1500	9	50	30/45	0.053/0.076	1400	1.05	0.90
2004	July-Sept	90	0	0	0.0	232.0									
2004	Oct-Dec	80	0.4	11.4	15.8	247.8									
2005	Jan-June	170	0.55	15.4	107.2	355.0	3300	1600	8	50	35/50	0.056/0.074	1450	1.10	0.90
2005	July-Dec	180	0	0	0.0	355.0									
2006	Jan-Mar	80	0.4	15.4	21.3	376.3									
2006	Apr-July	120	0.5	19.1	97.7	474.0	3600	1760	7	50	32/47	0.056/0.077	1650	1.15	0.95
2006	Aug-Sept	60	0	0	0.0	474.0									
2006	Oct-Dec	80	0.4	19.1	26.4	500.4									
2007	Jan-July	200	0.55	20.4	205.1	705.4	3600	1980	7	50	35/54	0.057/0.078	1550	1.15	0.95
2007	Aug-Sept	60	0	0	0.0	705.4									
2007	Oct-Dec	80	0.45	20.4	31.7	737.2									
2008	Jan-July	200	0.6	25	274.0	1011.1	4500	2000	6.5	50	35/50	0.057/0.082	1700	1.20	0.97
2008	Aug-Sept	60	0	0	0.0	1011.1									
2008	Oct-Dec	80	0.45	25	38.9	1050.0									
2009	Jan-July	200	0.6	25	311.0	1361.0	4500	2000	6.5	50	35/50	0.057/0.082	1700	1.20	1.00



# PEP-II Summary

- ◆ PEP-II has delivered 22 fb<sup>-1</sup> in Run 3 and 123 fb<sup>-1</sup> since May 1999.
- ◆ Starting to take advantage of FY2002 summer down projects. We still have several advances to go!
- ◆ Integrated luminosity is ahead of predicted track.
- ◆ Luminosity has increased to  $5.2 \times 10^{33} \text{ cm}^{-2}\text{s}^{-1}$ .
- ◆ Upgrades for Summer FY2003 are on track.
- ◆ Long range plans lead towards  $>2.5 \times 10^{34} \text{ cm}^{-2}\text{s}^{-1}$ .