



# SLAC Infrastructure and Power Issues



**Gregory A. Loew**

**DOE High Energy Physics  
Program Review**

**June 2-4, 2004**




# The SLAC Infrastructure

## What Does It Consist Of?

- About 350 buildings, labs, machine enclosures, roads
- Electrical utilities
- Cooling utilities
- Miscellaneous

## Problems and Needs:

- Original plant is almost 40 years old
- Replacements for original equipment and parts are no longer available
- Unfulfilled seismic standards need to be met for equipment protection (Major life threatening remediations have been completed)
- OSHA compliance issues will require remediation (Current estimate \$3M+)



# Sources of Funds

---

**GPP (Typically ~ \$4.2M/year in FY04 for HEP)**

**Some Operating Funds (~ \$1M/year)**


**Science Laboratory Infrastructure (SLI)  
(Starting in FY04)**

## Infrastructure Plan Categories

**Routine, Including OSHA Compliance**

**Revitalization**

**Seismic Remediation**



# SLAC Infrastructure Remediation Plan

- **Routine**

**Facilities Maintenance, Roofs and HVAC, Utilities Maintenance, ES&H Improvements and OSHA Compliance, ADA Compliance, and Programmatic Requirements**


- **Revitalization**

**(Replacement of original equipment)**


**Fire Alarms, Chilled Water Plant, HV Cables, 13 Variable Voltage Substations, Conventional Substations, Panel Boards (Linac), Various Switchgears, Motor Control Centers (Linac), Piping (Linac, BSY, RA)**

- **Seismic Remediation**

**About 350 buildings and structures: many still need to be seismically strengthened, some have been demolished.**



# SLAC Area Map




SLAC Area Map

12-2002  
6356A14

|  | Building Number | Grid Number |   | Building Number | Grid Number |
|--|-----------------|-------------|---|-----------------|-------------|
| Administration and Engineering Building (A&E)    | 41              | 30-C        | Light Fabrication Building                | 25              | 29-F        |
| Alpine Gate Guard House                          | 88              | 40-I        | Main Control Center (MCC)                 | 5               | 32-F        |
| Auditorium and Visitor Center                    | 43              | 31-C        | Main Gate (Information Booth)             | 83              | 31-B        |
| Auxiliary Control Building                       | 3               | 27-F        | Master Substation                         | 16              | 30-F        |
| Beam Switch Yard Access                          | 9               | 32-G        | Metal Storage Shelter                     | 29              | 29-F        |
| Cafeteria  | 42              | 31-C        | Parading Lots                             | A to G          |             |
| Central Hazardous Waste Management Area          | 245             | 27-G        | PEP Beam Facility/SSRL                    | 650             | 36-I        |
| Central Laboratory                               | 40/84           | 31-D        | PEP Beam Facility/SSRL                    | 730             | 37-C        |
| Central Utility Building                         | 23              | 31-D        | PEP Control Room                          | 685             | 33-H        |
| Chemical Storage Building                        | 36              | 29-E        | PEP Interaction Region 2 (IR-2)           | 620             | 38-D        |
| Cleaning Facility Building                       | 30              | 29-F        | PEP Interaction Region 4 (IR-4)           | 640             | 38-H        |
| Collider Experimental Hall (CEH)                 | 750             | 39-E        | PEP Interaction Region 6 (IR-6)           | 660             | 35-I        |
| Computer Building (SCS)                          | 50              | 32-E        | PEP Interaction Region 8 (IR-8)           | 680             | 32-H        |
| Controls Building                                | 34              | 28-F        | PEP Interaction Region 12 (IR-12)         | 720             | 35-B        |
| Cryogenics Laboratory                            | 6               | 33-E        | Physics and Engineering Building          | 280             | 29-D        |
| End Station A (ESA)                              | 61              | 34-E        | Plant Maintenance and Utilities           | 35              | 27-E        |
| End Station B                                    | 62              | 34-F        | Power Conversion                          | 15              | 29-G        |
| Environmental Protection Restoration             | 299             | 28-F        | Research Office Building (ROB)            | 48              | 30-B        |
| Environmental Safety and Health (ES&H)           | 24              | 28-E        | Sector 30 Guard House                     | 85              | 31-F        |
| Exercise Room/Shops Dining Room                  | 27              | 28-E        | SLC Engr. Trailer South (Fort Apache)     | 282             | 32-F        |
| Experimental Facilities Department Shops (EFD)   | 104             | 35-F        | SLC Offices                               | 212/214         | 31-E        |
| Fire Station                                     | 82              | 30-D        | SPEAR Control Room                        | 117             | 34-D        |
| Gate 17 Guard House                              | 86              | 33-D        | Stanford Synchrotron Radiation Lab (SSRL) | 120/131         | 34-DE       |
| General Services Building (Shipping & Receiving) | 81              | 26-E        | Test Beam Facility                        | 121             | 35-F        |
| Hazardous Waste Storage Area                     | 447             | 28-G        | Test Laboratory                           | 44              | 30-D        |
| Heavy Fabrication Building                       | 26              | 30-E        | User Office/Warehouse                     | 28              | 30-E        |
| Klystron Gallery (Visitors Alcove, Sector 27)    | 2               | 27-F        | Vacuum Assembly Building                  | 31              | 31-F        |
| Laboratory Offices and Shops (LOS)               | 137             | 33-E        | Visitor Center                            | 43A             | 31-C        |
| Light Assembly Building                          | 33              | 28-E        | Warehouse/User Offices                    | 28              | 30-E        |

## SLAC Infrastructure Plan


| Infrastructure  | FY04       | FY05        | FY06        | FY07       | FY08        | FY09        | FY10       |
|---|------------|-------------|-------------|------------|-------------|-------------|------------|
| <b>Routine</b>  |            |             |             |            |             |             |            |
| Facilities Maintenance, Utilities Maintenance, ES&H Improvements and OSHA Compliance, ADA Compliance, and Programmatic Requirements   |            |             |             |            |             |             |            |
| Landlord (HEP)  | 3.8        | 2.2         | 2.5         | 2.6        | 3.0         | 3.6         | 4.3        |
| HEP   | 0.5        | 1.7         | 0.8         | 0.8        | 0.5         | 0.4         | 0.0        |
| BES (FY05 includes \$1.5M XLAM const.)  | 0.2        | 2.0         | 0.7         | 0.7        | 0.5         | 0.7         | 0.3        |
| <b>Subtot Routine (OP/GPP)</b>  | <b>4.4</b> | <b>5.9</b>  | <b>4.0</b>  | <b>4.0</b> | <b>3.9</b>  | <b>4.7</b>  | <b>4.6</b> |
| <b>Revitalization</b>   |            |             |             |            |             |             |            |
| (Replacement of original equipment)   |            |             |             |            |             |             |            |
| Fire Alarms, Chilled Water Plant, HV Cables, 15 Variable Voltage Substations, Conventional Substations (Overall), Panel Boards (Linac), Various Switchgears, Motor Controls Centers (Linac), Piping (Sewer, Hot and Cold Water, LCW). |            |             |             |            |             |             |            |
| Landlord (HEP)  | 0.3        | 0.2         | 0.6         | 0.6        | 0.2         | 0.0         | 0.0        |
| HEP   | 0.2        | 0.8         | 0.8         | 0.9        | 0.7         | 0.3         | 0.0        |
| BES   | 0.2        | 0.1         |             |            | 0.2         |             |            |
| <b>SC Lab Infrastructure (SLI)</b>  | <b>1.3</b> | <b>3.8</b>  | <b>2.8</b>  |            | <b>5.0</b>  | <b>5.0</b>  | <b>3.0</b> |
| <b>Subtot Revitalization (OP/GPP/SLI)</b>   | <b>2.0</b> | <b>4.9</b>  | <b>4.2</b>  | <b>1.5</b> | <b>6.1</b>  | <b>5.3</b>  | <b>3.1</b> |
| <b>Seismic Remediation</b>  |            |             |             |            |             |             |            |
| About 350 buildings and structures: many still need to be seismically strengthened, a number have been demolished, and a few will have to be replaced.  |            |             |             |            |             |             |            |
| Landlord (HEP)  | 0.2        | 0.1         | 0.1         | 0.3        | 0.3         | 0.3         | 0.3        |
| HEP   | 0.3        | 0.1         | 0.4         | 0.0        | 0.5         | 0.5         | 0.5        |
| BES   | 0.0        |             |             |            |             |             | 0.4        |
| <b>SC Lab Infrastructure (SLI)</b>  | <b>1.1</b> | <b>3.3</b>  | <b>3.7</b>  |            |             |             |            |
| <b>Subtot Seismic (OP/GPP/SLI)</b>  | <b>1.5</b> | <b>3.5</b>  | <b>4.2</b>  | <b>0.3</b> | <b>0.8</b>  | <b>0.8</b>  | <b>1.2</b> |
| <b>HEP</b>  | <b>5.2</b> | <b>5.2</b>  | <b>5.2</b>  | <b>5.2</b> | <b>5.2</b>  | <b>5.2</b>  | <b>5.2</b> |
| <b>BES</b>  | <b>0.4</b> | <b>2.1</b>  | <b>0.7</b>  | <b>0.7</b> | <b>0.7</b>  | <b>0.7</b>  | <b>0.7</b> |
| <b>SLI</b>  | <b>2.4</b> | <b>7.1</b>  | <b>6.5</b>  | <b>0.0</b> | <b>5.0</b>  | <b>5.0</b>  | <b>3.0</b> |
| <b>Total Funding</b>  | <b>8.0</b> | <b>14.4</b> | <b>12.3</b> | <b>5.8</b> | <b>10.8</b> | <b>10.8</b> | <b>8.8</b> |



# OSHA Compliance Issues

## EXAMPLES

- **Machine guarding upgrades**
- **Circuit breaker, junction box, outlet and other electrical upgrades**
- **RF and other electrical equipment grounding**
- **Cable tray upgrades**
- **Exposed voltage energized equipment upgrades**
- **SLAC training in use of electrically energized equipment**
- **Stairways, fixed ladders and fall protection upgrades**
- **Secondary containment upgrades**
- **Illicit storm drain connections and sewer repairs**
- **Formal inspections of hoisting equipment**
- **Fire alarm and extinguisher upgrades**
- **Signs and lighting upgrades**
- **NRTL inspection program**



# Infrastructure Line Item Construction Projects

## Science Laboratories Infrastructure (SLI)


### **SLAC Safety and Operational Reliability Improvements (TEC \$15.6M; \$2M start in FY04)**

The proposed project will improve the safety and operational reliability of the Laboratory's facility and systems by specifically identifying and upgrading the most critical sections of all failing mechanical utility systems, and by selectively upgrading the most important mission-critical experimental and manufacturing facilities that are seismically deficient. SLAC's piping systems for natural gas, compressed air, low-conductivity water (LCW), cooling tower water (CTW), chilled water (CHW), hot water (HW), fire protection water (FPW), sewer and storm drainage serve over 200 buildings used for offices, laboratories, shops support, storage, heavy and light fabrication, and above- and below-ground experimental research facilities including LINAC, PEP-II, BaBar, FFTB, Test Accelerator, GLAST and SPEAR. Since these piping systems were installed almost 40 years ago, and are prone to leaks and failures that can no longer be prevented by good maintenance, the potential is high for serious disruptions of mission-critical research, and safety and environmental hazards. The mechanical utilities upgrade proposed is necessary for SLAC to continue to provide first-class research facilities, cost effectively, while complying with its ES&H requirements. Furthermore, since SLAC is located in a seismically active geographic area, the seismic upgrade efforts will enhance SLAC's ability to survive major earthquakes by improving the seismic strength of several important research and infrastructure facilities. While no one knows when the next major earthquake will strike the San Francisco Bay Area, geologists predict that the probability of such an earthquake during the next 30 years is 67%.

### **Electrical Utilities Reliability Upgrade (Proposal) (TEC ~\$13M; FY08 start)**


The proposed project will upgrade the existing electrical utility systems in the two-mile linear accelerator (LINAC), which is the source of high energy electron or positron beam for many of the planned experimental scientific programs. The LINAC electrical systems, consisting of motor control centers, panel boards, variable voltage transformers and substations, were all installed at the time when SLAC was originally built, almost 40 years ago. The equipment is obsolete and replacement parts are no longer available. In addition, the equipment is not in compliance with the current electrical codes. Failure of the circuit protection devices to work properly can result in either collateral damage for failure to open or unplanned interruptions of operation. This project will upgrade the below 600 volt essential electrical utility systems in the LINAC.





# Cooling Utilities


- **6 Cooling Towers Total**
  - 3 replaced so far and 1 new one built (GPP)**
  - 1 still to be replaced (SLI)**
  - 1 OK for now**
- **Underground Piping (SLI)**
  - Natural gas, compressed air, low conductivity water, cooling tower water, chilled water, fire protection water, sewers, storm drains**



# Seismic Remediation (26% of original 1999 plan completed so far with GPP)

## SLI Projects

- **PEP Mechanical Buildings**
- **CT101**
- **CT Huts**
- **CT 1701 Basin**
- **B050 Computer Center**
- **B044 Klystron Test Lab**
- **SSRL B120**
- **SSRL B140**
- **SSRL SPEAR Shielding**
- **End Station A Upgrade**
- **End Station B Upgrade**
- **Beam Dump East Tunnel**



# Electric Utilities (% Replacement)

**One Major Substation (85 MW), two  
AC Lines (230 kV, 69 kV) Transforming  
Down to 12.4 kV (100%)**

**12.4 kV distribution feeders (85%)**

|                   |               |               |
|-------------------|---------------|---------------|
| <b>Switchgear</b> | <b>12.4kV</b> | <b>(100%)</b> |
|                   | <b>480 V</b>  | <b>(15%)</b>  |


## **Proposed SLI Program (FY 08-10)**

**13 (out of 16) Variable Voltage Substations ( SLI) (0%)  
(others built out of GPP)**

**Conventional Substations (SLI) (5%)**

**Motor Control Centers (SLI) (0%)**

**Panel Boards (SLI) (0%)**




# Variable Voltage Substations (16)



**12kV Input Section with Transformer**




**600 V Distribution Section and Controls**




# SLAC MII Projection

|   | <b>RPV</b>   | <b>FY04</b>  | <b>FY05</b>  | <b>FY06</b>  |
|---|--------------|--------------|--------------|--------------|
|   | <b>(\$M)</b> | <b>(\$M)</b> | <b>(\$M)</b> | <b>(\$M)</b> |
| Non-Programmatic Buildings<br>and OSF             | \$267.0      |              |              |              |
| Indirect Funded Maintenance                       |              | \$4.3        | \$4.2        | \$4.4        |
| GPP (Replace major systems,<br>e.g., roofs, HVAC) |              | <u>\$0.4</u> | <u>\$0.8</u> | <u>\$1.0</u> |
| Total Maintenance and Sustainment<br>Activities   |              | \$ 4.7       | \$5.0        | \$ 5.4       |
| <b>MI I = Total Sustainment Activities/RPV</b>    |              | 1.8%         | 1.9%         | 2.0%         |




# Electric Power, Present and Future

- **In the foreseeable future, when the B-Factory and SPEAR3 are running, SLAC will use between 50 and 60 MW peak**
- **Currently, power is bought via DOE/LLNL/LBNL/SLAC Consortium, from**
  - WAPA (Sacramento) 77.6 MW at under \$30/MWh**
  - Pacificorp (Portland) 53 MW at \$32/MWh**
  - 130.6 MW**
- **On January 1, 2005, the contract between PG&E and WAPA, which has provided for this relatively inexpensive power to the Consortium, will expire**
- **To prepare for the future, DOE, via a Memorandum of Agreement between the NNSA and the Office of Science, is now going to market with a Utility Procurement Plan (UPP) via WAPA to constitute a portfolio of power supplies for the next five-to-ten years or so.**



# Electric Power, Present and Future, cont.


- **Final bids from private utilities will hopefully be received and firmed up by August 2004**
- **Rates are likely to be between 70% and 100% higher than current rates**
- **The increase in the SLAC/HEP power budget for FY 2005 is estimated to be between \$6M and \$7M**
- **An additional cost uncertainty stems from the fact that PG&E will no longer be obligated to transmit the power to SLAC at the current wholesale transmission rate**



# SLAC Electric Power Costs

|                      | FY2000 | FY2001 | FY2002 | FY2003 | Est<br>FY2004 | Est<br>FY 2005 |
|----------------------|--------|--------|--------|--------|---------------|----------------|
| Site Power (K\$)     | 573    | 670    | 861    | 837    | 818           | 1461           |
| HEP Power<br>(K\$)   | 5153   | 6014   | 7871   | 8351   | 7332          | 13216          |
| SSRL Power<br>(K\$)  | 661    | 717    | 1,017  | 657    | 1077          | 2202           |
| Total Power<br>(K\$) | 6387   | 7401   | 9750   | 9845   | 9226          | 16879          |
| GWh                  | 326    | 316    | 334    | 363    | 361           | 360            |
| \$/MWh               | 20     | 23     | 29     | 27     | 26            | 47             |





# DOE Northern California Sites

## Annual Peak Demand and Energy Forecasts

**2005-2014**

| <b>YEAR</b> | <b>PEAK DEMAND</b> | <b>ENERGY</b> |
|-------------|--------------------|---------------|
|             | <b>(Kilowatts)</b> | <b>(MWh)</b>  |
| 2005        | 134,000            | 779,000       |
| 2006        | 135,000            | 995,000       |
| 2007        | 144,000            | 1,006,000     |
| 2008        | 151,183            | 1,070,133     |
| 2009        | 154,445            | 1,090,878     |
| 2010        | 154,830            | 1,094,297     |
| 2011        | 155,409            | 1,098,231     |
| 2012        | 155,891            | 1,101,903     |
| 2013        | 156,469            | 1,105,838     |
| 2014        | 156,951            | 1,108,912     |