PEP-II Status and Plans

M. Sullivan
for the PEP-II Team
DOE High Energy Physics Program Review
June 2-4, 2004


Outline

- Improvements over the last year
- Present Status
- Plans for the present run (Run 4)
- Plans for summer 2004
- Luminosity improvements and upgrade plans


The PEP-II e⁺e⁻ asymmetric collider



PEP-II ring layout




PEP-II Interaction Region and the BaBar Detector




Improvements last year

- Status last June
 - Peak luminosity: 6.6×10³³
 - Number of bunches: 1034 (by3 pattern)
 - I⁺ current 1550 mA (3 RF stations)
 - I current 1175 mA (7 RF stations)
 - Fill and coast both beams
 - $-\beta_{v}^{*}$ of 12 mm
- Status now:
 - Peak luminosity: 9.2×10³³
 - Number of bunches: 1588 bunches in the by2 (24 long trains)
 - Parasitic collision effects seen (<5%), ECI effects small (<2%)
 - I⁺ current 2450 mA (3 RF stations)
 - I-current 1550 mA (8 RF stations)
 - All data now taken in trickle charge mode (both beams)
 - $-\beta_v^*$ of 10.5 mm


"Typical" running day in November 2003 at PEP-II Before Continuous Injection



Continuous Injection (Trickle Charge) Both Beams




Peak luminosity of 9.21 x 10³³



Record Peak Luminosity

Daily Integration Record



PEP-II Records

1550 mA HER


Last update: June 1, 2004

Peak Luminosity

May 21, 2004


Integration records of delivered luminosity

Best shift (8 hrs, 0:00, 08:00, 16:00)	246.3 pb ⁻¹	May 21, 2004
Best 3 shifts in a row	710.5 pb ⁻¹	May 24, 2004
Best day	710.5 pb ⁻¹	May 24, 2004
Best 7 days (0:00 to 0:00)	4.258 fb ⁻¹	May 14-May 20, 2004
Best week (Sun 0:00 to Sat 24:00)	4.194 fb ⁻¹	May 16-May 22, 2004
Peak Ave Lum	8.705×10^{33}	May 14, 2004
Best 30 days	16.045 fb^{-1}	Apr 28 – May 27, 2004
Best month	16.019 fb ⁻¹	May 2004
Total delivered	225 fb^{-1}	




Last updated: 6/1/2004 7:32

PEP-II Monthly Integrated Luminosity





Last Updated: 6/1/2004 7:32

PEP-II Daily Average for each Month









Improvements in run 4

- Lower LER β_v^* from 11 to 10 mm (is down to 10.5 mm)
- Lower HER β_v^* from 11 to 10 mm (is down to 10.5 mm)
- Commission new HER RF woofer
- Increase HER current to 1480 mA (have gotten to 1550 mA)
- Increase LER current to 2500 mA (have gotten to 2450 mA)
- Shorten HER bunch length by raising HER RF voltage
- Shorten LER bunch length by raising LER RF voltage
- Fix HER beta beat
- Lower LER β_x*
- Online model updates and online correction tools
- Use HER/LER octupoles
- Improve lattice corrections (orbit, dispersion ...)

Overall Parameters and Goals

Twice design

Parameter	Units	Design	Best in collision	Future 2007 gøal	
l+	mA	2140	2450	4500	
I-	mA	750	750 1550		
Number bunches		1658	1588	1715	
β_y^*	cm	15-20	11	8	
ξ _y		0.03	0.05, 0.08	0.055-0.08	
Luminosity	x10 ³³	3.0	9.2	24	
Integrated Iumi / day	pb ⁻¹	130	710	1800	

Over three times design

Over five times design!

Near Term Goals for Run 4

 This run's near term goal is to deliver at another 15 fb⁻¹ and reach 1 x 10³⁴ before the summer shutdown (end of July 2004).

 We also want to demonstrate the capability for delivering 850 pb⁻¹ per day.

Summer 2004 PEP-II Improvements

- IR2 south forward shield wall
- Add another new LER RF station
- Add a HER RF station by splitting up a current 4 cavity station into two 2 cavity stations
- Two new "Frascati" longitudinal kickers in LER
- New electrodes for transverse kickers

Shorter bunches

- Add fans to all HER bellows
- Alignment work (quadrupole rolls)
- New LER synchrotron light monitor
- IR NEG pump HOM reduction
- New Support Tube Chiller

New transverse kicker electrodes



New Longitudinal Feedback Kicker Assembly



PEP-II Long Range Upgrade Plans

- Lower β_v* from 11 to 8mm
- Raise LER beam current from 2.4 to 4.5 A
- Raise HER beam current to 1.4 to 2.2 A
- Increase number of bunches to 1715+
- Complete hardware by Fall 2006
- Reach peak luminosity by Summer 2007

Increase luminosity to 2.4×10³⁴ cm⁻² sec⁻¹

PEP-II Future Luminosity Parameters

	β_{x}	β_{y}	εχ	ϵ_{y}	n	I	σ_{x}^{*}	σ_y^*	Lumi	ξ _x	ξ _y
Units	cm	mm	nm	nm		mA	μ m	μ m	x1E33		
LER now	43	11	30	1.3	1588	2450	114	3.8	9.21	0.065	0.069
LER 2007	28	8	60	1.35	1715	4500	130	3.3	24.0	0.071	0.078
HER now	33	11	60	1.4	1588	1450	141	3.9	9.21	0.045	0.045
HER 2007	28	8	60	1.4	1715	2200	130	3.3	24.0	0.050	0.056

Future luminosity increase factors

Parameter	Present	Future	Luminosity gain ratio	Hardware and work needed
LER current	2450 mA	4500 mA		Two RF stations, new vacuum chambers
HER current	1550 mA	2200 mA -	1.61	Two RF stations, new vacuum chambers
β_y^*	11 mm	8 mm	1.38	HER higher tunes, RF & power supplies work
ξ _y	0.068 L 0.045 H	0.079 L 0.053 H	1.16	Tune plane, coupling, & IR work
Parasitic ∆x	3.22 mm	3.80 mm	1.08	B1 magnet change
Total			x 2.78	

PEP-II Long Range Beam Parameters Goals

- April 2004: 2.3A x 1.4 A β_v *=11 mm 1555 bunches L=8.4E33
- July 2004: 2.5A x 1.6 A β_v *=10 mm 1600 bunches L=10E33
- June 2005: 3.3A x 1.8 A β_v *=9 mm 1700 bunches L=15E33
- July 2006: 3.9A x 2.0 A β_v *=8 mm 1720 bunches L=20E33
- July 2007: 4.5A x 2.2 A β_v *=8 mm 1720 bunches L=24E33

- With good integration reliability and trickle injection:
- 115 fb⁻¹ more integrated from Summer 2003 to Summer 2004.
- 530 fb⁻¹ total integrated by Fall 2006.
- About 1.7- to 2.0 ab⁻¹ integrated by Fall 2010.

Summer-Fall 2005 PEP-II Shut-Down Activities

- Install LER-5 RF station
- Install HER-10 RF station
- Remove support tube for SVT work
- Increase beam separation with stronger B1 permanent magnet
- Upgrade several high-power IR vacuum chambers (Be bellows, Q4, Q5, high power dump, Q2 bellows, LER abort window, radial ion pump, luminosity chamber, ...)
- HER lattice upgrade for low momentum compaction
- LER quadrupole power supply upgrades for lower β_y*
- New RF comb filters


IR Modifications

- We think we can get to 8 mm β_y^* without any major hardware changes in the near IR
- Vacuum chamber heating from SR power at the higher beam currents looks OK so far
- SR masking for detector backgrounds is OK
- We presently see beam effects from the 1st parasitic crossing in the by2 pattern. Presently, we can correct most of this effect and get back the lost lumi. The parasitic crossing effect is made worse with lower β_y *s. Can we still compensate?

IR modifications (cont.)

- Looking at upgrading B1 magnets to improve the 1st parasitic crossing effect
- Keep the B·dl the same. Strengthen the inside magnetic slices and weaken or remove some of the outside slices.
- Need a rad hard magnetic material with a higher field strength
- Build new radial ion pumps
- Build new Q4 and Q5 HER beam pipes

PEP-II Interaction Region



Conclusions

- PEP-II has reached a luminosity of 9.2×10³³. It has delivered to BaBar 710/pb in one day.
- BaBar has collected well over 200 fb⁻¹
- We trickle inject into both rings all of the time now
- We plan to deliver another 15 fb⁻¹ and reach 1×10³⁴ before the summer shutdown
- We have a new challenge from the director 850 pb⁻¹ per day capability before the summer shutdown
- Near term upgrades are going well
- Planned upgrades toward 2.4×10³⁴ are on track
- Need to complete specifications for a few items over the next two months for the 2004 and 2005 downs:
 - Several IR vacuum chambers
 - HER lattice upgrade path
 - B1 magnet upgrade path
 - NEG pump upgrade